

Implementation of and deployment of a large scale programme – Magnetometers

**Felicity Lockett
Transport for London**

20th September 2013



Contents

- SCOOT Project – The background
- Magnetometer System – The basics
- Project Structure
- Planning Processes
- Installations
- Lessons Learnt




The Project

- Programme milestone of 1000 SCOOT commissionings by end of March 2013
- Ultimate target of benefits reported at 1000 sites by end of 2013
- Reportable to the DfT
- New SCOOT detection at 115 locations for final year of the New Investment SCOOT Programme
- Olympic delivery workload lead to compressed delivery period



Magnetometers – The Basics

A wireless system of vehicle detection



Magnetometers – Why Use Them?


Cost – whole life-cycle savings of 60% predicted vs inductive loops. Also, TfL's Lane Rental initiative added to the cost of major road works.

Time – minor works permits required as opposed to major permits for duct runs

Disruption – post-Olympics many projects were competing for road space, magnetometer installation is low impact.




Project Team Structure



Project Timeline

Y4 2012-13 SCOOT Programme – Next Stage Plan – Key Tasks, Metrics & Milestones



Supply Chain

- Supplier appointed in late July
- Periodic meetings held to:
 - » Forecast equipment levels – “just in time” delivery
 - » Agree processes for delivery and return of goods
 - » Forum for technical support / feedback



Training

- Basic training in design principles in May; follow up on installation given in October

Design Engineers

- Traffic Infrastructure
- Network Performance

Installation Engineers

- Traffic Infrastructure
- Signals Contractors x3

Maintenance Engineers

- Maintenance Inspectorate
- Signals Contractors x3




Preparing for installations

- Draft guidance note on installation prepared and circulated to contractors and internal staff
- Rates of installation agreed with contractors
- Procedure for handover into maintenance devised
- 33 London Boroughs and TfL Street Lighting departments contact and process for permission to mount repeaters agreed



Preparing for installations

- Sites packaged geographically and programmed for installation in clusters




Installation

- First sites from programme installed and commissioned in November
- Supplier provided technical support during installation of each contractor's first two sites
- A typical installation took three days:
 - Day 1 & 2 – installation of equipment
 - Day 3 – configuration




Drawing Details



MAGNETOMETER'S FOR OTU: 07/001

NUMBER	DISTANCE FROM N/S KERB	DISTANCE TO STOPLINE (METRES)	REFERENCE POINT	PROPOSED OR EXISTING
SD0	4.0	180.0	IN LINE WITH PARTY WALL #278/280	EXISTING
SD1	2.5	118.0	ADJACENT OF PARTY WALL 38-40	EXISTING
SD2	2.5	132.0	UPSTREAM OF PARTY WALL #297/299	EXISTING
SD3	2.5	158.0	IN LINE WITH PARTY WALL #67/69	EXISTING
SD4	3.0	180.0	IN LINE WITH PARTY WALL #306/308	EXISTING



ACCESS POINT/ REPEATER	SIGNAL POLE/ LAMP COLUMN	LOCATION
AP1	P4	SIGNAL POLE 4
AP2	P1	SIGNAL POLE 1
AP3	P1	SIGNAL POLE 1
AP4	P2	SIGNAL POLE 2
RP1	LC	LC#17
RP2	LC	LC#08199
RP3	LC	LC#10
RP4	LC	LC#04202
RP5	LC	LC#06202



Equipment mounting height

- AP mounted on signal pole ~3.7m above ground
- Repeater mounted 3.5m-4.0m above ground
- 200m range found to be too long in some instances




Cable terminations

Cables direct to card



Cables terminated in sockets




Signal Strength

- Default sensitivity settings not always appropriate – resulted in a series of detectors with intermittent faults
- Currently carrying out analysis of performance of recommended sensitivity settings vs reduced sensitivity



Signal Strength

- High voltage of Piccadilly Line caused disruption to wireless signals at two junctions



Mobile Access Point



Used for:

- Monitoring of sensor activation
- Changing of remote units RF channels
- Taking signal strength measurements
- Scanning for an unknown sensor
- Proving Access Points and interface cards



Lessons Learnt

- Trial process needed to be better specified and with clear outcomes
- Training for maintenance engineers was too generic – it needed to cover the likely faults and difficulties that would arise
- Training given too early – too much of a time separation between design training and start of design



Output from the Project

- More accurate cost model for future business cases – RSM SCOOT
- Design and installation document
- Revised commissioning procedure to ensure robustness of wireless network
- Fault finding guide to assist maintenance engineers
 - Mobile access point



Questions

